#### Workshop on

"Current and Emerging Methods for Optimising Safety and Efficiency in Nuclear Decommissioning" Sarpsborg / Norway / 2017











# SAFE DISMANTLING OF THE SVAFO RESEARCH REACTORS R2 & R2-0 IN SWEDEN

Dirk Schneider
Hans-Uwe Arnold

Back End Germany Reactor D&D AREVA Paul-Gossen-Str. 100 D - 91058 Erlangen





#### SVAFO R2 Dismantling Content

- Historical background
- Scope of Work
- Radiological Characterization
- Waste Routes
- Planned Sequence
- Safe Working Area
- Safe Dismantling
- (Un-) expected Challenges
- ▶ Preliminary vs. Final Packing Plan
- Results & Lessons Learned





# **SVAFO R2 Dismantling Historical background**

- AB Atomenergi ordered the facility by Allis-Chalmers (USA)
- ▶ Time of operation:1960 to 2005
- Three sister facilities were built; whereof two facilities are still in operation: Safari (RSA) and Petten (NL)
- ▶ R2 and R2-0 reactors are in a three-part pond (150m³)
  - R2: 30MW, upgrade in 1969: 50MW
  - ◆ R2-0: 1MW
- Purpose: neutron experiments, material behavior
  - Test of fuel elements under BWR/PWR conditions
  - Isotope production for medical / industrial applications
  - BNCT radiotherapy
- 2010 Nuclear license transferred from Studsvik to SVAFO
- 2012 SVAFO R2 dismantling project started
- ▶ 2014 Decommissioning plan etc. approved by SSM
- ▶ 2014 Contract for dismantling and packing of the reactors (June)
- ▶ 2015 Completion. 3 pools were cleared from reactors R2-0, R2 and surroundings





### **SVAFO R2 Dismantling Scope of work**

#### Phase 1


- Dismantling / cutting of R2-0
- Removal of all R2 support equipment
- Dismantling / cutting of R2
- Emptying of pools
- Packaging, transport, documentation

H9/10 penetration — through liner


Reactor R2 — H3, H4, H5, H6, H7, H8 — penetrations through liner

penetration

Direction to north



- Experienced Swedish Partners
   Pool cooling system-
- Reliable technical solutions
- Combined FAT & Training with customer



Concrete structure




Combining AREVA's expertise in D&D with the knowledge of the former operators and with experienced Swedish on-site team securing effective performance



### **SVAFO R2 Dismantling Radiological Characterization**

up to 100Sv/h expected







#### **SVAFO R2 Dismantling Waste Routes**

Waste Route 1 DR: > 2 Sv/h



**Baskets for WR 1** 

- Size: Ø 160mm x 760mm
- Weight: max. 25kg load
- Loading of baskets under water

▶ 7 baskets, 87kg

► Waste Route 2

DR: 2 Sv/h ... 2 mSv/h



#### **Cassettes for WR 2**

- Size: 810mm x 810mm x 800mm
- Weight: max. 3.400kg
- Loading of baskets under water

▶ 24 cassettes, 8.753kg

Waste Route 3

DR: < 2 mSv/h



#### Handling according to WR 3

- Max. size: 2.5m x 1.0m x 1.0m
- Lifting, rinsing and packing in plastics

▶ 3.561kg





#### SVAFO R2 Dismantling Example for optimized Packaging

Waste Route 1


DR: > 2 Sv/h

► Waste Route 2

DR: 2 Sv/h ... 2 mSv/h


Waste Route 3

DR: < 2 mSv/h



► 1 TN<sup>®</sup> MW cask AREVA TN

« All in One Solution »



► 6 CBF-KB pack units AREVA TEMIS



Handling according to WR 3


- Max. size: 2.5m x 1.0m x 1.0m
- Lifting, rinsing and packing in plastics

► 3.561kg





- Create a safe working arrangement
  - Wall protection
  - Bottom protection
  - Working table
- Dismantling of R2-0
- Dismantling of R2















#### Dismantling of R2






















#### Dismantling of R2











#### Dismantling of R2











#### Dismantling of R2

#### **SVAFO R2 Dismantling Planned Sequence**






**Core box** 




forward-looking energy



Dismantling of R2











Removal of R2 reactor connections to the bioshield, close wall penetrations, unbolt flange connections in Pool 1







forward-looking energy



Protection of pool bottom & walls avoids leakages












Safe working distance = table inside platform















- Platform and working table in Pool 2
  - Handling rods
  - Rack for safe storage






# **SVAFO R2 Dismantling Safe Dismantling**

#### ► Cutting of R2-0 in Pool 2










# **SVAFO R2 Dismantling Safe Dismantling**

#### Dismounting work in Pool 1









#### **SVAFO R2 Dismantling Safe Dismantling**


#### Cutting of Upper Vessel













- Dismounting work in Pool 1
  - confined working conditions, 73mm "free" space
  - Sensitive handling essential (Al liner)





### **SVAFO R2 Dismantling**

- **Challenges**
- **Safety Measure** 
  - Self-construction of a pneumatic balancer for sensitive lifting tasks
  - **Recognizes stuck or jammed load:** 
    - no damages
  - Compensates the weight of the component:
    - gives feeling while handling

















- Pendular hacksaw combined with shear
  - Application of Plan B solution
  - Removal of stainless restraint structure
  - Components with mechanical stress













#### Intervention tool

- Planned Plan C solution
- Contact Arc Metal Cutting (CAMC)
- Confined accessibility:90mm from bottom, 70mm from wall liner
- Only solution: cut through lamella with graphite electrode








- Inspection of as-build situation
  - Rod handled camera (12m long)
  - Cardanic wrench socket prolongation joined TV controlled










R2-0 & R2	masses
Aluminium	5.400kg
Stainless steel	6.000kg
Peripheral equipment	1.000kg
total	12.400kg

reactor	pieces
R2-0	88
R2	257
total	345

WR	WR	delta
WR1	WR2	270kg
WR2	WR3	808kg
WR2	WR1	47kg
	total	1.125kg

#### **SVAFO R2 Dismantling**Results

- ▶ No accidents
- Personnel dose below estimation
- Huge amount of small pieces
  - Container with bigger volume








#### **SVAFO R2 Dismantling**Results

Originally planned layout (10pc.)

Realized layout (28pc.)



No detailed Preliminary Packing Plan necessary, one final only!






#### **SVAFO R2 Dismantling**Results







No detailed Preliminary Packing Plan necessary, one final only!





#### **SVAFO R2 Dismantling Lessons Learned**

- Build a "Decommissioning Team"
- Prepare a thorough "Radiological Characterization"
- Replace the legacy operation systems with new, flexible "Decommissioning Support Systems"
- Close communication to the Back Office
- Use the wide AREVA experiences from D&D of PWR and BWR, which are also valid for RTR.
- Use AREVA services all along the D&D project avoiding interferences in the chain:
  - scenario definition characterization sampling cutting sorting conditioning - cask supply - logistic



#### More information:

Hans-Uwe Arnold

Phone: +49 9131 900 91823 Mobile: +49 160 88 78 500

Mail: <u>uwe.arnold@areva.com</u>

**AREVA GmbH** 

Back End Germany Reactor D&D AREVA Paul-Gossen-Str. 100 D - 91058 Erlangen

Editor and Copyright [2016]: AREVA GmbH – Paul-Gossen-Straße 100 – 91052 Erlangen, Germany. It is prohibited to reproduce the present publication in its entirety or partially in whatever form without prior written consent. Legal action may be taken against any infringer and/or any person breaching the aforementioned prohibitions.

Subject to change without notice, errors excepted. Illustrations may differ from the original. The statements and information in this brochure are for advertising purposes only and do not constitute an offer of contract. They shall neither be construed as a guarantee of quality or durability, nor as warranties of merchantability or fitness for a particular purpose. These statements, even if they are future-orientated, are based on information that was available to us at the date of publication. Only the terms of individual contracts shall be authoritative for type, scope and characteristics of our products and services.

